BRUHAT BANGALORE MAHANAGARA PALIKE

BBMP/2020-21/OW/WORK_INDENT43730

APPROVED SCHEDULE - B

No.EE/BTP/BBMP/E-PMT/05/2020-21, Date: 27-07-2020

Name of Work:Construction of RCC Drain and Culverts at Bharathnagara Abubakar Masjid road in ward no 06 Byatarayanapura Sub Division

Sl. No.	Approved Qty.	Description	Unit	Approved Tender Rates of M L DHANANJAYA ( )	
				In Figures	In Words
1	2470.23	KSRRB 300-1. Earthwork excavation by manual means for roads, drains & similar works in ordinary soil excavated surface levelled and sides neatly dressed, the disposed earth to be levelled neatly after breaking of clods complete as per specifications. Item No. 19.1/ PWD SR 2018-19	Cum	144.66	Rupees One Hundred Forty Four and Sixty Six Paise Only
2	143.55	KSRRB M2100-10. Providing and laying Plain cement concrete of mix 1:3:6 with OPC @ 220kgs, with crushed 40mm and down size graded granite metal coarse aggregates @0.89cum and fine aggregates @ 0.46cum, in foundation mechanically mixed, placed in foundation and compacted by vibration including curing for 14 days including cost of all materials, labour, HOM curing, form works, scaffolding and centering complete as per specifications. (PWD SR 2018-19 (Page No. 222, Item No. 27.18)	Cum	5691.91	Rupees Five Thousand Six Hundred Ninety One and Ninety One Paise Only
3	52.8	Providing and constructing granite / trap / basalt size stone masonry in basement with cement mortar 1:6, edges of stones chistle dressed in courses not less than 15 cms high, bond stones at two m. apart in each course including cost of materials, labour, HOM, scaffolding, curing complete as per specifications. KBS 5.1.13 Page No. 255/ Item No. 34.9/ PWD SR 2018-19	Cum	6101.42	Rupees Six Thousand One Hundred One and Forty Two Paise Only
4	2400	KSRB 4-6.4 : Providing and removing centering, shuttering, strutting, propping etc., and removal of form work for vertical surface such as walls at any thickness, including attached pilasters, buttresses, plinth cills and string courses cost of all materials, labour complete as per specifications. Specification No. KBS 4.6.(PWD Sr 2018-19 P 16 It 4.31)	Sqm	398.38	Rupees Three Hundred Ninety Eight and Thirty Eight Paise Only
5	17.55	KSRB 4-1.7 : : Providing and laying in position plain cement concrete of mix 1:3:6 withOPC cement @ 220kgs, with 20mm and down size graded granite metal coarse aggregates @0.84cum and fine aggregates @0.56cum machine mixed, concrete laid in layers not, exceeding 15cms, thick, well compacted, in foundation and plinth, including cost of all materials, labour, HOM of machinery, curing complete as per specifications. Specification No. KBS 4.1,4.2/P No. 13/ Item No. 4.7/ PWD SR 2018-19	cum	5907.79	Rupees Five Thousand Nine Hundred Seven and Seventy Nine Paise Only
6	66	KSRB 15.1.3: Providing FLush pointing to coursed stone masonry with cement mortar 1:3, 20 mm deep, after raking joints to depth of 20mm nicely lining, including cost of materials, labour, curing complete as per specifications. Page No. 115/ Item No. 15.1/ PWD SR 2018-19	Sqm	156.9	Rupees One Hundred Fifty Six and Ninety Paise Only
7	283.95	KSRRB M2200-5.9. Providing and laying Design mix M20 with OPC @ 320kgs, with 20mm and down size graded granite metal coarse aggregates @0.69cum and fine aggregates @ 0.46cum, with superplastisiser @3lts confirming to IS9103-1999 Reaffirmed-2008 including cost of materials, labour, HOM curing, form works, scaffolding and centering complete as per specifications /Page No. 227 Item No. 28.7.9, PWD SR 2018-19	Cum	5756.45	Rupees Five Thousand Seven Hundred Fifty Six and Forty Five Paise Only
8	19.88	KSRRB M2200-6. Providing T.M.T. steel reinforcement for R.C.C. work including straightening, cutting, bending, hooking, placing in position, lapping and/or welding wherever required, tying with binding wire and anchoring to the adjoining members wherever necessary complete as per disign (laps, hooks and wastage shall not be measured and paid) cost of materials, labour, HOM complete as per specification. TMT Bar Fe-500, Page No. 229/ Item No. 28.8.2, PWD SR 2018-19	Tonne	75928.86	Rupees Seventy Five Thousand Nine Hundred Twenty Eight and Eighty Six Paise Only
9	82.5	Providing and fixing RCC precast cover slab of 250mm thick made out of CC 1:2:4 and jelly 20mm and down size with steel reinforcement, including form work, lift charges, curing and concrete finished surfaces on both sides etc, complete and as per drawing and the directions of Engineer in-charge. (Data Rate)	Sqm	5687.82	Rupees Five Thousand Six Hundred Eighty Seven and Eighty Two Paise Only
10	813.6	Providing and fixing RCC precast cover slab of 100mm thick for drain in cement concrete 1:1.5:3 using graded granite jelly 20mm and down size with steel reinforcement, including form work, lift charges, curing and concrete finished surfaces on both sides etc, complete and as per drawing and the directions of Engineer in-charge. (Data Rate)	sqm	2453.38	Rupees Two Thousand Four Hundred Fifty Three and Thirty Eight Paise Only
11	2470.23	KSRRB M100-2. Loading and Unloading of stone boulders by manual means complete as per specification MORTH-100/chapter-1 Page No. 136/ Item No. 17.1/ PWD SR 2018-19	Cum	74.56	Rupees Seventy Four and Fifty Six Paise Only

Signature of the Contractor

Executive Engineer
Byarayanapura Division
BBMP, Bangalore - 92

10/12

10/12